Grand Alliance digital HDTV System Cable Test Results

Performed - June 01 to June 09
Both 8 VSB and 16 VSB Systems Tested

CubbleLotm

Composite Third Order

8 VSB

Target Test Result <25 dB 27 dB

16 VSB

Target <38 dB Test Result 35 dB

CableLabee

Carrier to Noise

8 VSB

Target Test Result <15.6 dB

16 VSB

Target Not Specified Test Result 29 dB

CableLabes

CableLabs®

Phase Noise

8 VSB

Target <81 dB Test Result 78 dB

16 VSB

Target <87 dB Test Result 82 dB

Cable Lobs

Residual FM

8 VSB

Target >6.5 kHz Test Result 9 kHz

16 VSB

Target >4 kHz Test Result 7 kHz

CableLabee

Channel Change

8 VSB

Target 0.7 sec Test Result 0.7 sec

16 VSB

Target 0.7 sec Test Result 1.1 sec

CableLabe

Local Oscillator Instability

8 VSB

Target

±89 kHz

Test Result ±100 kHz

16 VSB

Target Test Result ±89 kHz 100 kHz

Burst Error Correction

8 VSB

Target Test Result

>169 μsec @10 Hz 180 μsec @ 10 Hz

16 VSB

Target >129 μsec @ 10 Hz Test Result 120 μsec @ 10 Hz

CableLabee

Acknowledgments

Thanks to:

Grand Alliance Members Advanced Television Test Center Staff CableLabs Staff

Grand Alliance digital HDTV System Cable Field Results

Performed July 28 to August 29 8 VSB Signal Received Off-air 16 VSB Signal on Cable Systems

Cobletable

8 Time Warner Systems Tested
Various bandwidths and vintages
Am Fibre Links
No microwave AML's

CableLabes

ATV Channel 53 Received Off-air
Signal Error Corrected
Second Data Stream Added
16 VSB Modulation for cable system
ATV Signal Added where spectrum was available

Cable Labe

Direct Feed to ATV Receiver

At or Above Threshold at 35 Sites

3 bad sites on System operating 3 Channels above design Frequency

Cobbei ober

Signal Fed Through HIAB Before ATV Receiver

Signal below Threshold at 9 Locations

ATV signal above normally maintained frequencies on 2 Systems (3 test points)

ATV Signal located above system design frequency of 2 Systems (6 test Points)

CableLabee

Conclusions

16 VSB ATV System operates error free if Cable System meets FCC Specifications

ATV System continued to operate if signal level was b∋low FCC specifications until receiver threshold reached.

Cable Labor

CableLabs®

Acknowledgments

Thanks To:

Grand Alliance Members PBS and Field Test Personnel CableLabs Staff & Consultant

Cable Late

CableLabs®